Unofficial English translation, made for demonstration purposes. Layout simplified; this is not the original document. Original: tijhuisingenieurs.nl/files/ti20332-pres-03-technieken-bij-de-pilots-1-v2.pdf

North side South side

approx. 2 m

North side South side

approx. 2 m

North side South side

4.0

North side South side

4.0

North side South side

Techniques used in the pilots

Pilot 1 Water reed

This legakker lies almost entirely under water. The field is in the northern Kievitsbuurt. The aim is to develop the field into reed land.

Method

We install an open revetment with a waling at the waterline.

This creates an underwater basin.

We are testing 2 different techniques:

1. We place dredged material in the underwater basin.

2. We do not place any dredged material.

Pilot 3 Management measures

The aim is for kraggen (floating reed islands) to form. This is a quiet location in the southern Kievitsbuurt.

Method

We prune the current field and remove the stumps.

We create additional openings in the existing revetment on the south side, making it easier for land reed to grow out into the water.

Technique 1 Technique 2 Photo of location

Photo of location

Pilot 2 Linking two fields

These two fields will be connected to each other by reed islands with reed and reed banks on the south side of the fields. The fields are in the southern Kievitsbuurt.

Method

We prune the current field and remove the stumps.

We are testing 2 different techniques:

1. On the south side, approx. 4 m in front of the current bank, we place a row of piles with boards. In this we place a floating structure with reed and aquatic plants.

2. On the south side, we place a row of piles with brushwood in between. Between the rows of piles, we place anchored straw bales on which reed can grow.

Technique 1 Technique 2 Photo of location